


WYANGALA DAM WALL RAISING PROJECT



Agenda

- Acknowledgement of Country
- Introductions
- Project update
- Environmental assessment update
- Engagement
- Connect with us
- Questions

WaterNSW





Background

Since late 2019 we have been developing the project

- Finalising the concept design
- Field work almost complete
- Procurement for a new Wyangala Water Treatment Plant
- Shortlisting of main construction proponents
- Preparation of inputs for final business case
- Engaging with stakeholders, communities and Aboriginal parties
- Establishing a project office





2014

NSW Government funds a feasibility study into Cranky Rock Dam

Federal Government identifies new dam on Belubula River (Needles Gap) for feasibility investigations

Lachlan identified as priority catchment under NSW State Infrastructure Strategy

2015

Feasibility study phase 1 recommends a further study into build and non-build options

2016

Feasibility study - phase 2 investigations continue

2017

Feasibility study - phase 2 investigations continue

2018

Feasibility study (phase 2) completed

June

Wyangala Dam Wall Raising project identified in 20-year Infrastructure Options Study

NSW Government provides funding for project's final business case

2019

NSW Government lists project in Critical Needs (Water Supply) Act 2019

NSW and Commonwealth Governments announce funding for project

2020

Concept design started

Environment Impact Statement preparation and assessments started

Site investigations and environmental field studies started

Landholder engagement started

Community information sessions and webinars started

4 WaterNSW

Background



Key benefits

- Increase storage capacity of the dam by 53%
- Significantly improves:
 - drought resilience
 - Water reliability
 - flood attenuation
- Increases capability to manage high inflow/flood events
- 5 WaterNSW




Confirmed FSL



Confirmed 10m Full Supply Level

- Environmental Impact Statement
- Final business case
- Concept design
- Holiday Park planning work



WaterNSW

2021 activities





Environmental field surveys and investigations continue



Landholder engagement continues



Community information sessions and webinars continue



Environmental Impact Statement public display for consultation



Final business case developed



Construction partner procurement



Detailed design starts



Construction of Water Treatment Plant at Wyangala starts



Construction planning for Holiday Parks finalised

New Water Treatment Plant



Project progress

- Benefits
- 'No regrets' project
- Planning pathway
- Procurement Enviropacific Services
- Construction and commissioning




Procurement process

WaterNSW

Alliance partnership development

- Shortlisted two separate contractors, Acciona and **Seymour Whyte** for main construction work
- Appoint successful main construction work contractor
- Start main construction delivery



Construction



Construction staging program

- Dam must remain operational
- Manage operation and construction safety
- Construction is expected to take up to four years

Clay and rock required

- Materials to be sourced locally and as close to project site as possible
- Considering expanding rock quarry used for previous dam construction



Stage 1 - Preparing downstream foundation

Stage 2 – Placing downstream rock fill

Stage 3 – Removing existing dam crest

Stage 4 – Start raising dam wall

Stage 5 – Finish raising dam wall

Construction



Workforce accommodation

- Dedicated local construction workforce accommodation
- Investigating former dam construction workforce accommodation site
- Dedicated workforce between 100 and 300 – additional indirect workforce




Previous construction workforce accommodation

Safety and our approach



- Risk management
- Contractor selection
- Safety expectations
- Behaviours in community
- Working together



Dam Safety Management



- Dam safety risk profile to be maintained throughout
- Dam safety emergency management plans updated to be reflective of the operations and management at each stage of construction
- This will include any modification to the operational (and air space) rules
- Emergency management plans and protocols will be shared with the Local **Emergency Management Committee at** each stage throughout the project



Environmental assessment



Key features

- 10m increase in Full Supply Level
- Modify spillway to suit new FSL and embankment
- Modify intake towers to suit new FSL
- New saddle dam near the entrance of Wyangala Waters Holiday Park



Further detail







Operation


Flood

- Downstream flood model assess conditions under design storm events under existing and proposed dam operations.
- Enhanced operational flexibility to manage flood events

Water quality, cold pollution and algae

- Modify existing towers to provide multiple intake points
- This reduces impacts from cold water pollution






Ancillary work

Future activities

- Relocating existing public and private roads and infrastructure (blue)
- Building new Reids Flat bridge to be above 1 in 10 flood level
- Relocating facilities within both Wyangala Waters and Grabine Lakeside Holiday Parks





Environmental update



Specialist studies update



Terrestrial biodiversity field work complete, assessment underway



Aquatic ecology field work complete, nons assessment underway



Aboriginal Cultural heritage upstream field work complete, assessment underway, downstream Cultural Values field work underway



Non-Aboriginal heritage field work complete, draft assessment complete



Traffic and transport assessment underway



Noise and vibration field work complete, draft assessment complete



Air quality field work complete, draft assessment complete



Health impacts assessment underway



Contamination and soils draft assessment complete



Hydrology modelling and assessment underway



Flood modelling and assessment underway



Environmental Sustainable Development (ISCA) draft assessment complete



Landscape and visual impact draft assessment complete



Social impacts assessment underway



Waste draft assessment complete




Climate change risk and greenhouse gas draft assessment complete

Biodiversity


Our approach

- NSW Biodiversity Assessment Method (BAM)
- Producing a Biodiversity Development Assessment Report (BDAR)
- Assessing impacts to listed threatened species and ecological communities, migratory species, and wetlands of international importance
- Targeted flora and fauna seasonal surveys (between April 2020 – January 2021)
- Biodiversity offset strategy investigations underway
- Department of Agriculture, Water and Environment (DAWE) has determined controlled action (EPBC Act) and assessed under the Bilateral Agreement





Aquatic Ecology





We have

- Used DPI Fisheries data
- Then carried out targeted fish habitat surveys
- Identify habitat potentially impacted
- Consider options to minimise or mitigate impacts to aquatic fauna
- Prepare a detailed assessment
- Develop an offset strategy based on residual impacts
- Ongoing engagement with DPI Fisheries

Heritage and Cultural Values



Our work so far

- Cultural heritage in accordance with DECCW 2010
- 15 Registered Aboriginal Parties (RAPs)
- Update on Aboriginal Cultural Heritage Assessment Report (ACHAR) progress is:
 - Project methodology consultation with RAPs complete
 - Subsurface test excavations upstream with RAPs complete
 - Field surveys with RAPs to be complete 2021
 - Analysis of materials underway
 - Preparation of an ACHAR underway
 - Consultation with RAPs and Aboriginal Stakeholders ongoing
- Cultural heritage survey focuses on values upstream and downstream of the dam ongoing
- Cultural values interviews with Aboriginal elders, Local Aboriginal Land Councils and RAPs to be complete 2021


Social impact

WaterNSW

What is covers

- Describe existing social environment
- Involve targeted interviews
- Assesses impacts and benefits during construction and operation
- Recommend measures to mitigate and manage identified impacts
- Be prepared in line with leading practice

Note: Cumulative impacts being considered (two construction workforces - the dam and Cowra Hospital)



Hydrology and Flooding



River System Modelling


- What is the day to day behaviour of the river basin system both existing and proposed
- Numerous inputs
- Outputs relevant to the project

Flood Modelling

- Design storm event based
- Focuses on flood events
- Quantifies downstream hydraulics in more detail
- Represents up to extreme flood events
- Uses field survey
- Includes downstream and upstream



Inundation levels to date







Ancillary work

Ancillary work impact areas and activities include:

- Relocating existing public and private roads and infrastructure (blue)
- Relocating facilities within both Wyangala Waters and Grabine Lakeside Holiday Parks









Reids Flat



Localised impacts and potential mitigations

Early key impacts identified for Reids Flat during construction, if the project is approved include:

- Traffic
- Noise and vibration
- Flooding
- Social




Construction traffic - routes



Proposed route to construction area

- Primary route (blue) to the construction area via Darby Falls Road from Cowra and then via a new haulage road across spillway into compound area
- Vehicle movements required along green route for proposed saddle dam and possible clay borrow sites
- Heavy vehicle movements for rock materials to use a dedicated project route orange to avoid them being on public roads
- Use of Reg Hailstone Way has been identified to be limited to light vehicles only



Construction traffic - volumes



Traffic volumes (still being confirmed)

- Vehicle movements would be for:
 - Deliveries of equipment
 - Deliveries of materials
 - Workforce arrivals and departures
 - Workforce, equipment and materials moving between construction areas



Traffic – potential mitigation



Mitigation design and construction planning

- Diverting movements off public roads and away from villages
- Completing road safety audit to identify issues along routes

Mitigation curing construction

- Construction Traffic Management Plan including traffic control plans
- Examples of mitigation measures used on major projects include:
 - Tracking of vehicles for location and speed
- Restricting movements at school start and finishing times
- Moving oversized equipment and plant at night where possible including NSW Police supervision
- Restricting movements during peak holiday periods

Noise and vibration - methodology



We have

- Undertaken noise and vibration assessment in accordance with relevant guidelines
- Undertaken monitoring for background noise levels at:
 - Wyangala Waters Holiday Park
 - 58 Waugoola Road (in village)
 - 185 Trout Farm Road (west of dam)
 - 3542 Darby Falls Roads (south-west)
- Undertaken a quantitative assessment for construction including modelling potential noise levels
- Undertaken a qualitative assessment for operation unlikely to be a change in noise level for dam operations





Construction noise impacts



Summary of preliminary modelling in areas

- Road work Construction work for realignments and improvements may cause exceedances;
 Impacts about 53 receivers within 800 metres
- Reids Flat Construction work for bridge may cause exceedances; Impacts about 15 receivers within 700 metres
- Vegetation Removal work may cause exceedances; Impacts properties at Wyangala,
 Wyangala Waters and Grabine Lakeside holiday parks and Oaky Creek Road in close proximity
- Road traffic Not predicted to exceed criteria
- Blasting Proximity and size of charge may cause some exceedances; Impacts to be considered in Blast Management Plan

Noise – potential mitigation



Mitigation design and construction planning

- Adjusting work areas to increase distance to nearest properties, where possible
- Timing noisy work outside particularly periods (avoid holiday periods)

Mitigation during construction

- Noise and Vibration Management and Blast Management plans
- Examples of mitigation measures used on major projects include:
 - Ongoing consultation
 - Notify community of noisy activities
 - Out of hours works procedure
 - Respite periods
 - Reduce noise at source (equipment and plant)
 - Structure condition surveys (vibration impact areas)

Social

Project-specific plans

- Industry participation plan
- Workforce management plan
- Communication management plan
- Temporary workforce accommodation plan
- Aboriginal engagement plan

Strategies for wellbeing including participation in sporting and community groups and access to mental health services

Cowra Police will also be consulted in developing a worker Code of Conduct and workforce policies associated with use of the club.









Landowner

meetings





WHAT'S HAPPENING IN MAY?

- Our quarterly project newsletter will be published for the community, stakeholders and businesses.
- Preliminary Environmental Impact Statement we are holding early localised input sessions in person 17, 18, 19 and 20 May at Wyangala, Woodstock, Darbys Falls, Reids Flat and Bigga. For event details and to RSVP, click here.
- Our next round of Community Information Sessions will be held in person at Crookwell and online 11, 12, 13 and 21 May. For event details and to RSVP, click here.

Connect with us





Wyangaladamproject @waternsw.com.au



1800 735 822



Wyangala dam wall raising project community group



Waternsw.com.au

WaterNSW



Thank you



Questions



WaterNSW