



WYANGALA DAM WALL RAISING PROJECT

Project update


Woodstock
May 2021



Agenda

- Acknowledgement of Country
- Introductions
- Project update
- Environmental assessment update
- Engagement
- Connect with us
- Questions

WaterNSW



The background of the slide is a close-up photograph of numerous spherical water treatment media, likely anthracite or similar, in various shades of brown, red, and yellow. Some of the spheres are cracked open, revealing a porous, yellowish interior. In the bottom right corner, there are several long, green, pointed leaves, possibly from a plant like a water hyacinth.

Acknowledgement of Country

Background

Since late 2019 we have been developing the project

- Finalising the concept design
- Field work almost complete
- Procurement for a new Wyangala Water Treatment Plant
- Shortlisting of main construction proponents
- Preparation of inputs for final business case
- Engaging with stakeholders, communities and Aboriginal parties
- Establishing a project office



Background



Key benefits

- Increase storage capacity of the dam by 53%
- Significantly improves:
 - **drought resilience**
 - **Water reliability**
 - **flood attenuation**
- Increases capability to manage high inflow/flood events



Confirmed FSL



Confirmed 10m Full Supply Level

- Environmental Impact Statement
- Final business case
- Concept design
- Holiday Park planning work



2021 activities



Environmental field surveys and investigations continue



Landholder engagement continues



Community information sessions and webinars continue



Environmental Impact Statement public display for consultation



Final business case developed



Construction partner procurement



Detailed design starts



Construction of Water Treatment Plant at Wyangala starts



Construction planning for Holiday Parks finalised

New Water Treatment Plant



- 'No regrets' project
- Planning pathway
- Procurement – Enviropacific Services
- Construction & commissioning
- Benefits




Procurement process



Alliance partnership development

- Shortlisted two separate contractors, **Acciona** and **Seymour Whyte** for main construction work
- Appoint successful main construction work contractor
- Start main construction delivery



Construction



Construction staging program

- Dam must remain operational
- Manage operation and construction safety
- Construction is expected to take up to four years

Clay and rock required

- Materials to be sourced locally and as close to project site as possible
- Considering expanding rock quarry used for previous dam construction



Stage 1 - Preparing downstream foundation

Stage 2 – Placing downstream rock fill

Stage 3 – Removing existing dam crest

Stage 4 – Start raising dam wall

Stage 5 – Finish raising dam wall

Construction



Workforce accommodation

- Dedicated local construction workforce accommodation
- Investigating former dam construction workforce accommodation site
- Dedicated workforce between 100 and 300 – additional indirect workforce



Previous construction workforce accommodation

Safety and our approach



- Risk management
- Contractor selection
- Safety expectations
- Behaviours in community
- Working together



Dam Safety Management



- Dam safety risk profile to be maintained throughout
- Dam safety emergency management plans updated to be reflective of the operations and management at each stage of construction
- This will include any modification to the operational (and air space) rules
- Emergency management plans and protocols will be shared with the Local Emergency Management Committee at each stage throughout the project



Environmental assessment




Key features

- 10m increase in Full Supply Level
- Modify spillway to suit new FSL and embankment
- Modify intake towers to suit new FSL
- New saddle dam near the entrance of Wyangala Waters Holiday Park



Further detail




Operation

Flood

- Downstream flood model developed to assess the potential change in flooding conditions under design storm events between flood releases from the dam under existing and proposed conditions.
- Enhanced operational flexibility to manage flood events

Water quality, cold pollution and algae

- Modify existing towers to provide multiple intake points
- This reduces impacts from cold water pollution



Environmental update



Specialist studies update



Terrestrial biodiversity
field work complete,
assessment underway



Aquatic ecology
field work complete,
assessment underway



Aboriginal Cultural heritage
upstream field work complete,
assessment underway,
downstream Cultural Values
field work underway



Non-Aboriginal heritage
field work complete, draft
assessment complete



Traffic and transport
assessment underway



Noise and vibration
field work complete, draft
assessment complete



Air quality
field work complete, draft
assessment complete



Health impacts
assessment underway



Contamination and soils
draft assessment
complete



Hydrology
modelling and
assessment underway



Flood
modelling and
assessment underway



**Environmental Sustainable
Development (ISCA)**
draft assessment complete



**Landscape and
visual impact**
draft assessment complete



Social impacts
assessment underway



Waste
draft assessment complete




**Climate change risk
and greenhouse gas**
draft assessment complete

Biodiversity




Our approach

- NSW Biodiversity Assessment Method (BAM)
- Producing a Biodiversity Development Assessment Report (BDAR)
- Assessing impacts to listed threatened species and ecological communities, migratory species, and wetlands of international importance
- Targeted flora and fauna seasonal surveys (between April 2020 – January 2021)
- Biodiversity offset strategy – investigations underway
- Department of Agriculture, Water and Environment (DAWE) determined controlled action (EPBC Act) and assessed under the Bilateral Agreement



Aquatic Ecology



We have

- Used DPI Fisheries data
- Then carried out targeted fish habitat surveys
- Identify habitat potentially impacted
- Consider options to minimise or mitigate impacts to aquatic fauna
- Prepare a detailed assessment
- Develop an offset strategy based on residual impacts
- Ongoing engagement with DPI Fisheries

Heritage and Cultural Values



Our work so far

- Cultural heritage in accordance with DECCW 2010
- 15 Registered Aboriginal Parties (RAPs)
- Update on Aboriginal Cultural Heritage Assessment Report (ACHAR) progress is:
 - Project methodology consultation with RAPs – complete
 - Subsurface test excavations upstream with RAPs – complete
 - Field surveys with RAPs – to be complete 2021
 - Analysis of materials – underway
 - Preparation of an ACHAR – underway
 - Consultation with RAPs and Aboriginal Stakeholders - ongoing
- Cultural heritage survey focuses on values upstream and downstream of the dam – ongoing
- Cultural values interviews with Aboriginal elders, Local Aboriginal Land Councils and RAPs – to be complete 2021

Social impact



What is covers

- Describe existing social environment
- Involve targeted interviews
- Assesses impacts and benefits during construction and operation
- Recommend measures to mitigate and manage identified impacts
- Be prepared in line with leading practice

Note: Cumulative impacts being considered (two construction workforces - the dam and Cowra Hospital)



Hydrology and Flooding



River System Modelling


- What is the day to day behaviour of the river basin system - both existing and proposed
- Numerous inputs
- Outputs relevant to the project

Flood Modelling

- Design storm event based
- Focuses on flood events
- Quantifies downstream hydraulics in more detail
- Represents up to extreme flood events
- Uses field survey
- Includes downstream and upstream



Inundation levels to date



Ancillary work



Ancillary work impact areas and activities include:

- Relocating existing public and private roads and infrastructure (**blue**)
- Relocating facilities within both Wyangala Waters and Grabine Lakeside holiday parks



Woodstock



Localised impacts and potential mitigations

Early key impacts identified for Woodstock during construction, if the project is approved include:

- Construction traffic
- Social impacts during construction




Construction traffic - routes



Proposed route to construction area

- Primary route (blue) to the construction area via Darby Falls Road from Cowra and then via a new haulage road across spillway into compound area
- Vehicle movements required along green route for proposed saddle dam and possible clay borrow sites
- Heavy vehicle movements for rock materials to use a dedicated project route orange to avoid them being on public roads
- Use of Reg Hailstone Way has been identified to be limited to light vehicles only



Construction traffic - volumes



Traffic volumes (still being confirmed)

- Vehicle movements would be for:
 - Deliveries of equipment
 - Deliveries of materials
 - Workforce arrivals and departures
 - Workforce, equipment and materials moving between construction areas
- Initial one-way movements per day (worst case scenario):
 - Intersection of **Darby Falls Road south and Trout Farm Road:** about 25 light vehicles and 210 heavy vehicles
 - Entering **Wyangala Village** via west Sixth Avenue: about 250 light vehicles and 200 heavy vehicles
 - Along **Reg Hailstone Way:** about 50 light vehicles and no heavy vehicles



Traffic – potential mitigation



Mitigation design and construction planning

- Diverting movements off public roads and away from villages
- Completing road safety audit to identify issues along routes

Mitigation during construction

- Construction Traffic Management Plan including traffic control plans
- Examples of mitigation measures used on major projects include:
 - Tracking of vehicles for location and speed
 - Restricting movements at school start and finishing times
 - Moving oversized equipment and plant at night where possible including NSW Police supervision
 - Restricting movements during peak holiday periods

Social



Project-specific plans

- Industry participation plan
- Workforce management plan
- Communication management plan
- Temporary workforce accommodation plan
- Aboriginal engagement plan

Strategies for wellbeing including participation in sporting and community groups and access to mental health services

Cowra Police will also be consulted in developing a worker Code of Conduct and workforce policies associated with use of the club.



Wyangala Dam Wall Raising



 Improving long term water security and drought resilience in the Lachlan Valley

May 2021







ENGAGEMENT TO DATE

-  **Local community sentiment**
84% support
- 43** Community events  attendees **419**
-  **Registered Aboriginal Parties** **15**
-  **89** Stakeholder briefings
- 108**  Landowner meetings

LOCAL OPPORTUNITIES

- 315**  Local businesses registered
-  **10** Local businesses engaged

CONNECTING WITH YOU

- 333** Emails in  **6,950** Emails out
- 784** group members  **8** posts
9 comments
49 reactions
- 304** Calls in  **352** Calls out
- 24,689** Webpage views 
-  **368** Media stories
-  **22** Complaints received to date

WHAT'S HAPPENING IN MAY?

- Our quarterly project newsletter will be published for the community, stakeholders and businesses.
- Preliminary Environmental Impact Statement - we are holding early localised input sessions in person 17, 18, 19 and 20 May at Wyangala, Woodstock, Darbys Falls, Reids Flat and Bigga. For event details and to RSVP, [click here](#).
- Our next round of Community Information Sessions will be held in person at Crookwell and online 11, 12, 13 and 21 May . For event details and to RSVP, [click here](#).

Connect with us



Wyngaladamproject
@waterNSW.com.au



1800 735 822



Wyngala dam wall raising
project community group



WaterNSW.com.au



Thank you

Questions

